BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT21224

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/04/2015-16, Date: 01.02.2016

Improvements to roads, drains and Drilling borewells in ward no. 07 & 08 of Kodigehalli sub division of Byatarayanapura Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
1	6071.22	Removing B.S Slab of Drain and stacking	sqm	70	Rupees Seventy Only
2	5606.72	Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	86	Rupees Eighty Six Only
3	1724.5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete - 10.0 cms thick	sqm	874	Rupees Eight Hundred Seventy Four Only
4	7087.55	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	91	Rupees Ninety One Only
5	22533.4	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications.	sqm	97	Rupees Ninety Seven Only
6	4390.3	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification	cum	1885	Rupees One Thousand Eight Hundred Eighty Five Only
7	21970	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications.	sqm	14	Rupees Fourteen Only
8	21970	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqm over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications	sqm	77	Rupees Seventy Seven Only
9	17670	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications	sqm	3	Rupees Three Only
10	17670	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications.	sqm	16	Rupees Sixteen Only
11	104.52	Providing and laying bituminous macadum on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with FE loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (50 to 75mm) with 3.3% VG-30 bitumen.	cum	6000	Rupees Six Thousand Only

Signature of the contractor

01/06

Executive Engineer

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
12	1415.52	Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 509 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (30 to 45mm) with 6% CRMB-55	cum	12530	Rupees Twelve Thousand Five Hundred Thirty Only
13	6542.69	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading.	cum	86	Rupees Eighty Six Only
14	59.25	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications,	cum	175	Rupees One Hundred Seventy Five Only
15	259.8	Providing and laying heavy duty cobble stones 75 mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50 mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications	sqm	1115	Rupees One Thousand One Hundred Fifteen Only
16	261	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	93	Rupees Ninety Three Only
17	1	Providing Children Play Two Seater Standard Swing Equipment: This swing' consist of 2 Nos. seats of solid metal seats powder coated of Size-500mmx 250mm x 16 SWG supported by MS chains of Length 1.8mtrs, each seat is suspended by 1 line of chain. The chains are supported by circular housingswith bearing from which the chain in suspended. The beam is of 50mm MS tAt class pipe. Size of MS • chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and No. 1 24800.00 25300.00 28400.00 24000.00 -263.00.00 *·Lowestheight 2.00mtrs. The 2 Nos of cost iron-heads. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of superset paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift. loading. unloading and any other incidental charges and as per the drawing and specification and direction of the Engineer in charge of the work	No.	29040	Rupees Twenty Nine Thousand Forty Only
18	2	Providing Children Play Merry-Go-Round Equipment: Made of MS. 'A' class pipes. Main pillars are in 100mm, fitted with shaft and two bearings and other cross members are in 25 & 20mm MA 'A' Class pipes, bottom ring is made out of 25mm 0 ring size is 1.20 mtrs Dia, fitted with four seats are in mental sats of 250 x 200 x 18SGE, handles are made out of 20mm NB pipes and other supports are in 25mm MS 'N class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the Engineer In enarce of the work	No.	30800	Rupees Thirty Thousand Eight Hundred Only

Signature of the contractor

01/06

Executive Engineer

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
19	1	Providing Children Play Two Seater Swing Duck Equipment: This swing consist of 2 Nos. FRP Ducks supported by MS chains of Length 1.05mtrs, each duck Is suspended by 3 lines of chains. The chains are supported by circular housings with bearing from which the chain in suspended. The main beam is of 42mm MS 'A' class pipe. Size of MS chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and height 1.95mtrs. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat 0 protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the Enalneer in charae of the work.	No.	33880	Rupees Thirty Three Thousand Eight Hundred Eighty Only
20	10	Providing Sitting chairs made of RCC including steel reinforcement as per the directions of the Engineer-in-charge of the work	No.	7260	Rupees Seven Thousand Two Hundred Sixty Only
21	0.94	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5760	Rupees Five Thousand Seven Hundred Sixty Only
22	527.76	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification.	cum	6591	Rupees Six Thousand Five Hundred Ninety One Only
23	126	Supplying and fixing MS rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC 1:2:4 with 2 No. of 16mm dia MS hold fast rods each of length 25 cm, including cost of all materials, cutting, bending, scaffolding wherever necessary, nicely finishing the welded joints with all leads and lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Rm	1090	Rupees One Thousand Ninety Only
24	522	Providing and fixing MS block pipe of 38 mm dia of heavy gauge of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two vertical poles (MS rectangular poles) and spot welding the chain link with MS block pipe including cost of all materials, wastage in cutting and scaffolding wherever necessary with all lead and lift as directed by the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop paint	Rm	371	Rupees Three Hundred Seventy One Only
25	261	Providing chain link fencing 50mm size of 8 gauge properly stretched between existing rectangular poles and fixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop paint	sqm	767	Rupees Seven Hundred Sixty Seven Only
26	0.244	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making laster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	cum	119671	Rupees One Hundred Nineteen Thousand Six Hundred Seventy One Only
27	4.09	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures)	sqm	4348	Rupees Four Thousand Three Hundred Forty Eight Only

Signature of the contractor

01/06
Executive Engineer

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
28	6.24	Providing and fixing in position fully panelled Honne wood fully panelled shutters for windows with styles and rails of 35mm. thick, 75mm wide in two halves with panels of 25mm thick including cost of cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures)	sqm	5557	Rupees Five Thousand Five Hundred Fifty Seven Only
29	14.43	KSRB15-17 : Painting of wood surface KSRB 15-17.1 : Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	sqm	36	Rupees Thirty Six Only
30	14.43	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	sqm	94	Rupees Ninety Four Only
31	63.78	Dismantling weather proof course and removing and conveying the debris to a distance upto 200m	sqm	513	Rupees Five Hundred Thirteen Only
32	63.78	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. A. Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound over the RCC slab after cleaning the surface before treatment. B. Laying cement concrete using broken brick bats 25mm to 200mm size with 50% of cm 1:5 admixed with water proofing comund. C. proper curing. D. Finishing with 20mm thick joint less cm of mix 1:4, e. whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials, labour complete as per specifications	sqm	1000	Rupees One Thousand Only
33	8.4	Providing and fixing on wall surface 2.5kg / sq.cm H.D.P.E. rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, curing complete as per specifications.	Rm	556	Rupees Five Hundred Fifty Six Only
34	2	Providing fixtures - Door Lock	No.	441	Rupees Four Hundred Forty One Only
35	4	Providing fixtures - Handles power coated 150mm	No.	61	Rupees Sixty One Only
36	16	Providing fixtures - Hinges 5" heavy duty	No.	40	Rupees Forty Only
37	4	Providing fixtures - Tower bolt 300 mm long	No.	127	Rupees One Hundred Twenty Seven Only
38	11.42	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Qtl	5000	Rupees Five Thousand Only
39	74.7	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	331	Rupees Three Hundred Thirty One Only
40	346.9	Dismantling plastering and removing the debris with a lead upto 200m including cost of materials, labour, HOM of machineries complete as per specifications	sqm	25	Rupees Twenty Five Only
41	55.8	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	sqm	213	Rupees Two Hundred Thirteen Only

Signature of the contractor

Executive Engineer

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
42	103.67	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Inside wall)	sqm	258	Rupees Two Hundred Fifty Eight Only
43	159.47	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications	sqm	27	Rupees Twenty Seven Only
44	178.68	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	sqm	219	Rupees Two Hundred Nineteen Only
45	159.47	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications	sqm	76	Rupees Seventy Six Only
46	178.68	providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after toughly brooming the surface to remove all dirt and lose powdered material, free from mortar drops and other foreign matter cost of materials, labours, complete as per specifications with Primer	sqm	92	Rupees Ninety Two Only
47	178.68	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	92	Rupees Ninety Two Only
48	926.47	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications	cum	6817	Rupees Six Thousand Eight Hundred Seventeen Only
49	8.75	Providing and fixing of wall cladding using 20mm thick gang saw water cut granite in CM 1:3 proportion cut to required shape patron with paper joint finished with cement mortar using white cement and colour pigments to match the xcolour of slab making through jointing with sealant, making holes 25mm x 12mm grooves in joints including curing etc., complete	sqm	2587	Rupees Two Thousand Five Hundred Eighty Seven Only
50	1170.24	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5577	Rupees Five Thousand Five Hundred Seventy Seven Only
51	5265	Vacuum De-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift	sqm	106	Rupees One Hundred Six Only
52	351	Providing groove cutting for cement pavement with of 5mm to 10mm and depth 800mm-100mm including cost of cutting machine, generator and HOM of machinery, including cost of blade, coolant etc, including cleaning of groove and providing sand and hot bitumen fillers and filler metal etc including of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications	Rm	134	Rupees One Hundred Thirty Four Only

Signature of the contractor

01/06

Executive Engineer

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
53	1909.98	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Approved data rate enclosed)	sqm	1760	Rupees One Thousand Seven Hundred Sixty Only
54	140.94	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable ble material and stacking the serviceable material with all lifts complete as per specifications.- Rubble stone masonry in cement mortar	cum	275	Rupees Two Hundred Seventy Five Only
55	93.42	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable ble material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	cum	1146	Rupees One Thousand One Hundred Forty Six Only
56	158.4	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 N/sqmm with CM 1:4 masonry with solid concrete blocks of size 40x20x20 cm conforming to IS 2185 / 1965 in superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications	sqm	1120	Rupees One Thousand One Hundred Twenty Only
57	88.93	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications With Available stones	cum	4237	Rupees Four Thousand Two Hundred Thirty Seven Only
58	57.95	With New stones	cum	5675	Rupees Five Thousand Six Hundred Seventy Five Only
59	765	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	106	Rupees One Hundred Six Only
60	58.17	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification	cum	6039	Rupees Six Thousand Thirty Nine Only
61	469.07	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Qtl	4000	Rupees Four Thousand Only
62	6726.04	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	337	Rupees Three Hundred Thirty Seven Only
63	1592	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	No.	411	Rupees Four Hundred Eleven Only
64	1432	Providing and applying ready mix priming coat over concrete / masonry, / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour complete as per specifications.	sqm	29	Rupees Twenty Nine Only

Signature of the contractor

Executive Engineer

01/06

01/06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G N RAMESH	
				In Figures	In Words
65	1432	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry, / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour complete as per specifications.	sqm	74	Rupees Seventy Four Only

Signature of the Contractor

Executive Engineer 01/06
Byarayanapura Division
BBMP, Bangalore - 92

01/06